



NATIVE LAWN

INSTALLATION: STANDARD LANDSCAPE GRASS
GRASS TYPE: NATIVE LAWN
DESCRIPTION: DEEP GREEN YARN FIBERS ARE COMBINED WITH A DOWN TO EARTH TAN THATCH, TO ACHIEVE A DORMANT GRASS APPEARANCE.

SPECIFICATIONS:	
YARN	POLYETHYLENE
FILE WEIGHT	60 OZ./ SQ. YD.
DENIER	10,000
FILM TYPE	MONOFILAMENT-2 COLOR W/ THATCH
PRIMARY BACKING WEIGHT	8.25 OZ./ SQ.YD.
SECONDARY BACKING WEIGHT	20 OZ./ SQ.YD.
DIMENSIONAL STABILITY	NON-WOVEN MESH
BACKING CLOTH	NANOBAC
ANTI-BACTERIAL LAYER	RESISTANT TO MICRO-ORGANISMS
TOTAL WEIGHT	84.25 OZ./SQ.YD.
FINISHED PILE HEIGHT RANGE	1-3/4" (± 1/8") (NON-DIRECTIONAL)
TUFTING GAUGE	1/2"
PRIMARY BACKING	POLYPROPYLENE
SECONDARY BACKING	POLYURETHANE COATING
ROLL WIDTHS	15'
PERFORATION	EVERY 4"
MINIMUM REQ. TUFT BIND	8 LBS.
COLORS AVAILABLE	ROYAL GREEN & OLIVE W/ TAN THATCH

- INSTALLATION NOTES:**
- TURF MUST BE INSTALLED AND SEAMED WITH SURROUNDING ADJACENT PIECES RUNNING IN THE SAME DIRECTION. ALL SEAMS TO HAVE SEAMING GLUE & 6" WIDE SEAMING TAPE.
 - TO SECURE TURF AT BASE W/ 6" 60d FLAT HEAD GALV. NAILS 3-4' ON INT. FIELD. PERIMETER NAILER USE 1" TARPON SCRWS @ 9" O.C. ALONG PERIMETER.
 - RECOM'D MIN. INFILL 1/2" LB. COOL REFLECT NATURAL OR GREEN COATED SAND (OPT) AVAIL. IN 16 OR 20 MESH.
 - POWER BROOMING IS THE LAST STAGE OF TURF INSTALLATION.

- GENERAL NOTES:**
- INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH THE SPECIFICATIONS LISTED BY POLYTURF AUTHORIZED INSTALLERS.
 - DRAWINGS ARE FOR REFERENCE ONLY, DRAWINGS ARE NOT TO SCALE.
 - FOR FURTHER PRODUCT/ INSTALLATION INFORMATION VISIT WWW.POLYTURF.COM INFO@SUSTAINABLESURFACING.COM WWW.SUSTAINABLESURFACING.COM CONTACT (811) 288-0045